

## ADDENDUM ONE CHANGE IN SCOPE

Date: August 29, 2018

To: All Bidders

From: Annette Walton / Dianna Gilliland, Buyers  
AS Materiel, State Purchasing Bureau

RE: Addendum One for Request for Proposal Number 5911 Z1 to be opened September 27, 2018 at 2:00 p.m. Central Time

---

### Scope of Addendum

Section V. D. 1. A. will be superseded and replaced with the following:

The awarded Contractor may employ any felling cuts as needed to direct the fall of a tree to inflict the least possible damage to turf, roadways or surrounding vegetation. Once all directional and felling cuts are performed and the tree safely on the ground, the remaining stump shall be cut horizontally to a height no greater than 12 inches from the surrounding ground grade. If the grade is sloped, the remaining stump shall be no greater than 12 inches high on the up slope side. Upon safely felling the tree, the awarded Contractor will be required to buck/cross cut any large trunks and/or branches to a manageable size to facilitate the park staff to move such large diameter wood off of roads, trails or camping pads. The onsite Park Superintendent will communicate to the Contractor what a "manageable size" is defined as. This decision will be based on the Parks available equipment to remove large diameter wood off of roads, trails or camping pads. No additional clean-up is required. **Contractor should then remove the orange numbered tags from the felled tree and nail to the remaining stump.**

Section V. D. 10. will be superseded and replaced with the following:

**Contractor should leave the yellow numbering tags on the tree after their work is completed.** Park Superintendent or Agency Horticulturist will inspect the work completed before any payment or final payment can be submitted.

Cost proposal has been revised to remove two trees from the tree removal list. Please see revised Cost Proposal.

This addendum will become part of the ITB/proposal and should be acknowledged with the Request for Proposal response.

5911 Z1 Cost Proposal  
Tree Trimming /Pruning/Removal at Platte River State Park

Project: Tree Trimming / Pruning and Removal at Platte River State Park.

Firm: \_\_\_\_\_

Estimated Trees to be **Trimmed/Pruned** at Platte River State park – **Yellow Tags**

Tree Number	Location	Estimated DBH inches	Species	Quantity	Bidder Price
	<b>Owen Cabins</b>				
1	Owen #1, back, near SE corner	40	red oak	1	
2	Owen #1, back, near NE corner	34	bur oak	1	
3	Between Owen #1 and #2,	27	bur oak	1	
4	Owen #2, front, 20' north off entrance	32	bur oak	1	
5	Owen #3, 10' off east side	27	bur oak	1	
6	Owen #3, 10' off west side	18	bur oak	1	
7	Owen #3, 20' west off entrance	16	bur oak	2	
8	Owen #5, 6' off west side	15	bur oak	1	
9	Owen #8, 30' west off entrance	25	bur oak	1	
10	Owen #8, 15' north off entrance	27	bur oak	1	
11	Owen #9, front, 3' off entrance deck	46	bur oak	1	
12	Owen #11, back, 12' off SE corner	42	bur oak	1	
13	Owen #11, 15' south off entrance	25	bur oak	1	
14	Owen #11, 30' west off entrance	21	ash	1	
15	Owen #12, 20' south off entrance	33	bur oak	1	
16	Owen #13, 30' north off entrance	28	bur oak	1	
17	Owen #9, 100' SE off patio	42	bur oak	1	
18	Owen #8, 200' SE off patio	22	bur oak	1	
	<b>Day Use, picnic area south of tennis courts</b>				
19	100' south of tennis courts	19	bur oak	1	
20	200' SE of tennis courts	31	bur oak	1	
21	250' SE of tennis courts	21	bur oak	1	
22	80" SE of concrete pit toilet	24	bur oak	1	
	<b>Chokecherry cabins</b>				
23	Chokecherry #2, back, 30' west off patio	16	bur oak	1	
	<b>Crawdad Creek, Landscaped waterway</b>				
24	South end of sidewalk near switch back	37	bur oak	1	
25	along sidewalk	39	bur oak	1	
26	along sidewalk	40	bur oak	1	
27	Cottonwood cabin, 6' off of SE end	26	walnut	1	
	<b>Goldenrod cabins</b>				
28	Goldenrod #1, back, 60' west off back	23	red oak	1	
29	Golden Rod #3, back, 50' off south end	23	walnut	1	
30	Goldenrod #4, back, 50' off SE end	21	walnut	1	

	<b>Wild Turkey Cabins</b>				
31	Wild Turkey #1, 20' east off entrance	20	red oak	1	
32	Wild Turkey #1, 75' off east side	20	red oak	1	
33	Wild Turkey #2, 30' east off entrance	24	bur oak	1	
34	Wild Turkey #2, 30' east off entrance	18	bur oak	1	
35	Wild Turkey #3, 75' south off entrance	46	bur oak	1	
36	Wild Turkey #6, 30' SW off entrance	20	bur oak	1	
37	Wild Turkey #7, 45' south off entrance	30	bur oak	1	
38	Wild Turkey #7, 120 south off entrance	13	bur oak	2	
39	Wild Turkey Shelter, 40' south off end	22	bur oak	1	
40	Wild Turkey Shelter, 50' south off end	23	bur oak	1	
	<b>Whitetail cabins</b>				
41	Whitetail #2, back, 20' east off SE corner	19	bur oak	3	
42	Whitetail #3, side, 10' north off side	20	bur oak	2	
43	Whitetail #4, side, 10' east off side	28	bur oak	1	
	<b>Decker Creek Lodge</b>				
44	25' feet off SE corner	44	bur oak	1	
45	25' off north end	22	bur oak	1	
46	40' off north end	26	bur oak	1	
47	75' off north end	15	bur oak	1	
48	40' off west side	23	bur oak	1	
49	40' off west entrance	31	bur oak	1	
	<b>Trail betwn. Decker L. and Bison shelter</b>				
50	west side of trail	23	bur oak	1	
51	west side of trail	26	bur oak		
	<b>Bison Hollow Cookout area</b>				
52	Bison Hollow Cookout area	18	bur oak	1	
53	" "	25	bur oak	1	
54	" "	24	bur oak	1	
55	" "	18	bur oak	1	
	<b>Horse Trail, stables to Owen Crossing</b>				
56	Trail	60	bur oak	1	
57	Trail	40	bur oak	1	
58	Trail	20	bur oak	1	
59	Owen crossing	60	bur oak	1	
	<b>New glamping cabin area</b>				
60	near glamping cabin site	20	red oak	1	
61	near glamping cabin site	22	bur oak	1	
62	near glamping cabin site	20	red oak	1	
63	near glamping cabin site	20	bur oak	1	
<b>TOTAL TREE TRIMMING/PRUNING</b>					<b>\$</b>

Estimated Trees to be **Removed** from Platte River State Park – **Orange Tags.**

Tree Number	Location	Estimated DBH inches	Species	Quantity	Bidder Price
<b>Near Owen Cabins:</b>					
1	Owen #1, 50' south of entrance	14	dead, ash	1	
2	Owen #2, just off NE corner	32	ash	1	
3	Between Owen 2&3, 15' north of sidewalk	12	ash	1	
4	Owen #3, 50' south of entrance	15	ash	1	
5	Owen #4, near patio, 8' off east side	13	ash	1	
6	Owen #4, 20' SW of entrance	17	ash	1	
7	Owen #5, 15' off west side	12	bur oak	1	
8	Owen #6, back, 15' off east back side	21	dead, ash	1	
9	Owen #6, back, 15' off east back side	17	dead, ash	1	
10	Owen #7, front, 5' north of front entrance	16	bur oak	1	
11	Owen #9, front, 20' south of entrance	14	hackberry	1	
12	Owen #12, 8' off north side	11	bur oak	1	
13	Owen #13, back, 30' SE of back	22	bur oak	1	
14	Owen #13, back, 30' SE off back	26	bur oak	1	
15	Owen #12, back, 100' east off back	25	dead, bur oak	4	
16	Owen #9, 100' east off patio	18	dead, elm	1	
17	Owen #8, 100' SE off patio	17	ash	1	
18	Owen #8, 200' SE off patio	18	bur oak	1	
19	Owen #8, 200' SE off patio	22	mulberry	1	
20	Owen #4, 200' off back	20	dead, black cherry?	1	
<b>Craft Cabin, just south of lake dam</b>					
21	6' off SW corner of craft shelter	50	dead, cottonwood	1	
<b>Day Use, picnic area south of tennis courts</b>					
22	200' south of tennis courts	17	bur oak	1	
23	250' south of tennis courts	24	bur oak	1	
24	150' SE of concrete pit toilet	17	bur oak	1	
25	80' east of concrete pit toilet	18	ash	1	
<b>Amphitheatre</b>					
26	<del>80' west of amphitheater stage</del>	19	dead, broken ash	1	-No bid needed
<b>Red Cedar Cabins</b>					
27	Red Cedar #4, 50' west of entrance	12	ash	1	
28	Red Cedar #5, 20' west off back	16	ash	1	

29	Red Cedar Shower/latrine building, 50' north	20	ash	1	
30	Red Cedar Shower/latrine building, 40' north	28	ash	1	
31	Evergreen Cabin, 40' west	21	northern red oak	1	
32	Chokecherry Cabin #1, back, 15' west off SW corner	26	ash	1	
	<b>Crawdad Creek, landscaped stream feature</b>				
33	near sidewalk	22	mulberry	1	
34	west across bridge, west side of sidewalk	21	dead, elm	1	
35	west across bridge, west side of sidewalk	8	dead, ash	1	
36	west across bridge, west side of sidewalk	11	ash	1	
37	west across bridge, west side of sidewalk	18	dead, elm	1	
	<b>Golden Rod Cabins</b>				
38	Golden Rod #1, back, 80' west off back	12	Walnut	1	
39	Golden Rod #1, back, 100' west off back	19	ash	1	
40	Golden Rod #2, back, 10' south of patio	16	ash	1	
41	Golden Rod #2, back, 10' SW of patio	24	mulberry	2	
42	Golden Rod #3, back, 50' off south end	17	Walnut	1	
	<b>Wild Turkey Cabins</b>				
43	Wild Turkey #6, 38' SW off entrance	14	bur oak	1	
44	Wild Turkey #7, 60' south off entrance	17	bur oak	1	
45	Wild Turkey #7, 100' south off entrance	25	bur oak	1	
46	Wild Turkey Shelter, 20' west of SW corner	15	bur oak	1	
47	Meadowlark cabin, 15' SE off entrance	34	elm	1	
48	Bison Hollow Cookout area, 100' north of cabin	34	dead, elm	1	
	<b>Horse Trail, stables to Owen Crossing</b>				
49	100' SW of stables, near pedestrian bridge	16	mulberry	1	
50	start of trailhead, north of stables	18	Linden	1	
51	trail	38	bur oak	1	
52	trail	19	oak, dead	1	
53	trail	35	oak, dead	1	
54	trail	28	bur oak	1	
55	trail	12	locust	1	
56	trail	16	bur oak	1	
57	trail	14	bur oak	1	
58	trail	12	bur oak	1	

59	trail	12	oak, dead	1	
60	trail	13	oak, dead	1	
<b>New Glamping Cabin Area</b>					
<del>61</del>	<del>—near east glamping cabin</del>	<del>12</del>	<del>ash</del>	<del>1</del>	No bid needed
62	behind east glamping cabin	12	bur oak	1	
63	behind east glamping cabin	14	bur oak	1	
64	along road to east glamping cabin	10	elm	1	
65	along road to east glamping cabin	12	Walnut	1	
66	Red Cedar Cabin Loop, south of Evergreen cabin, 100 feet south of road	30	dead, oak	1	
<b>TOTAL TREE REMOVAL</b>					<b>\$</b>

Total Cost for Tree TRIMMING/PRUNING and Removal Project: \$ \_\_\_\_\_

OPTIONAL SERVICES WILL NOT BE EVALUATED FOR AN AWARD, THESE ARE OPTIONAL SERVICES THAT THE AGENCY CAN UTILIZE FOR ADDITIONAL WORK AS NEEDED DURING THE CONTRACT PERIOD.

OPTIONAL: ADDITIONAL TRIMMING/PRUNING PER TREE

APPROXIMATE SIZE DBH INCHES	COST PER TREE
10-15	
16-20	
21-25	
26-30	
31-40	
41-50	

OPTIONAL: ADDITIONAL REMOVAL PER TREE

APPROXIMATE SIZE DBH INCHES	COST PER TREE
10-15	
16-20	
21-25	
26-30	
31-40	
41-50	