



- ▶ (3) Cisco Cameras
 - (1) to be placed above the tv on the south wall (4 electrical lines/2 Cat6 cables)
 - (1) to be placed approximately 10' behind the placement of the projector (TBD) (4-gang recessed box/3 Cat6 cables)
 - (1) to be placed on the south angled wall, 7' above the stage (4-gang plate/2 Cat6 cables)
- ▶ (2) 75" tvs. Supplied by NDOT and placed on the south and north wall. Mounted approximately 56" from the floor
- ▶ (4) Ceiling speakers
- ▶ (1) Projector
- ▶ (2) Column speakers
- ▶ (2) BYOD wall plates
- ▶ (1) Projector screen
- ▶ (1) XLR-Record Output plate
- ▶ (1) Control Screen